



HIGH PRESSURE TEST PLUG - MAX

Dimensions

Equipment Weight - (kg).....: 1
Lifting/ Transportation.....: Transportation on pallet

Construction year

Built.....: 2020

Type

Item type.....: High pressure test plug
Fabricator.....: Curtiss Wright
Model.....: GTMAX-075P160

Flow / Pressure / Volume

P-max (bar).....: 1034
Nominal Pipe Size (Inches).....: 0.75
Nominal Pipe Schedule.....: 160
Plug Outside Ø (mm).....: 13.7
Range of use - Minimum (Ø mm).....: 14.5
Range of use - Max recom.(Ø mm): 16.0
P-max (PSI).....: 15000

Additional information

Equipment / Functions.....: Also suitable for 1/2" Schedule 40

Installation:
Normal Installation Torque : 34 Nm
Maximum Installation Torque : 54 Nm

I.D. sealing test plug for high pressure hydrostatic testing of pipe, pipelines and pressure vessels.